

NUMAR	SIMBOL ARTICOL U.M.	CANTITATEA	PU MATERIALE	V A L O R I
CURENT	LISTE ANEXE		PU MANOPERA	T O T A L E
	D E N U M I R E		PU UTILAJE	
	A R T I C O L		PU TRANSP.CF	
			GR.MAT./U.M.	GREUT.TOTALA (T)
1	2	3	4	5
INSTALATII ELECTRICE + INSTALATII DETECTIE				
1	RPEF19A1 BUC	38,000		
	DEMONTARE CORP ILUM SIMPLU			
	DULIE MEDIE			
2	EE04D1 BUC -ASIM	35,000		
	CORP DE ILUMINAT PANOU ECHIP.			
	CU SURSE LED 600/600			
3	EE04E1 BUC -ASIM	2,000		
	CORP DE ILUMINAT PENOU ECHIP			
	CU SURSE LED 600/300			
4	EE10J1 BUC -ASIM	3,000		
	12009-0001			
	CORP DE ILUMINAT TIP APLICA			
	DE TAVAN LED CU SENZOR DE			
	MISCARE			
5	EE12D1 BUC -ASIM	18,000		
	12009-0001			
	CORP DE ILUMINAT TIP APLICA			
	PERETE LED			
6	RPEE01A1 BUC	6,000		
	12010-0001			

	INLOC INTRERUPATOR MANUAL UNIPOLAR	
7	RPEE01G1 BUC 12010-0001 INLOC INTRERUPATOR MANUAL BIPOLAR	4,000
8	RPEE03A2 BUC INLOC PRIZA UNIPOL	9,000
9	RPEE03A4 BUC INLOC PRIZA BIPOL	27,000
10	ED08A1 BUC -ASIM 12017-0001 PRIZA DATE	13,000
11	ED11A1 BUC -ASIM 12025-0001 SENZOR DE MISCARE	7,000
12	RPEG01A1 BUC 12061-0001 INLOCUIT TABL ELECT PE PLACA MARMURA PE PERETE SAU IN NISE SUPRAFATA PLACA PINA LA 0 15 MP	2,000
13	ED12A1 BUC -ASIM 12025-0001 CORP DE ILUMINAT DE SIGURANTA EVACUARE-EXIT	9,000

14	ED12B1 BUC -ASIM	3,000
	12025-0001	
	CORP DE ILUMINAT DE SIGURANTA	
	EVACUARE-EVAC	
15	IA12D1 BUC -ASIM	1,000
	SISTEM PANOURI FOTOVOLTAICE	
16	ED10A1 BUC -ASIM	4,000
	12013-0001	
	BUTON DE ALARMARE	
17	ED13E1 BUC -ASIM	1,000
	12017-0001;12033-0001	
	SIRENA INTERIOARA	
18	ED13A1 BUC -ASIM	1,000
	12037-0001	
	SONERIE EXTERIOARA	
19	ED13B1 BUC -ASIM	10,000
	12037-0001	
	DETECTOR FUM	
20	IA01A1 BUC -ASIM	1,000
	CENTRALA INCENDIU	
21	EC03A1 M -ASIM	180,000
	12007-0001	
	CABLU DATE	

<hr/>		
22	EC02A1 M -ASIM	90,000
	12007-0001	
	CIRCUIT ELECTRIC ILUMINAT -EXT.	
<hr/>		
23	EA01A2 M	215,000
	TUB IZOLANT IP-PVC MONTAT	
	INGROPAT CU D=16MM	
<hr/>		
24	RPED02A1 M	215,000
	12007-0001	
	INLOCUIRE CABLU ENERGIE APARENT	
	CU SCOABE BACHELITA DIBLURI	
	LEMN SECTIUNEA CONDUCTELOR 4	
<hr/>		
25	EC05A1 M -ASIM	130,000
	12007-0001	
	CABLU JYStY 2X2X0,8MM E30	
	ROSU ECRANAT	
<hr/>		
26	ED08F1 BUC -ASIM	1,000
	12017-0001	
	PRIZA DE PAMANT	
<hr/>		
27	EH02A1 BUC	10,000
	INCERCAREA CABLURILOR PT.INST.	
	ELEC.DE COMANDA SEMNALIZARE SI	
	BLOCARI	
<hr/>		
28	EH05A1 BUC	2,000
	INCERCARE TABLOURI MARMURA CU	
	PESTE 6 CIRCUITE	
<hr/>		

INSTALATII SANITARE

29	RPSC16A1 BUC	2,000
	11402-0001;11405-0001	
	INLOC.COMPL.LAV.FAIAN.PORT.	
	SANIT.SEMI PORT.PE CONS.FIXAT	
	CARAM-BETON CU 1 ROB.TEAVA SCUR	
	PVC-U	
30	RPSC27A1 BUC	2,000
	11406-0001	
	INLOCUIREA UNUI VAS CLOSET DE	
	FAIANTA FONTA EMAILATA SAU	
	PORTELAN SANITAR TIP	
31	SC13A1 BUC -ASIM	1,000
	11406-0001	
	VAS PENTRU CLOSET DIN PORTELAN	
	SANITAR PT PERSOANELE CU	
	DIZABILITATI	
32	RPSC57A1 BUC	2,000
	INLOC.OGLINDA SANIT.DE	
	SEMICRISTAL CU MARGINILE	
	DIMENS.DE 400X500MM PE PER.CAR	
	.BET	
33	RPSC66A1 BUC	2,000
	13929-0001	
	INLOC.SUP.HIRTIE FONT.EMAIL.	
	PORT.SAN.TABL.DECAPOTDA	
34	RPSA02A1 M	60,000
	DEMONTARE TEVI OTEL ZINC EXIST	
	PAM 1 2-1 TOLI	
35	SB43A1 BUC	2,000
	SIFON DE PARDOSEALA COLECTOR	
	CONFECT DIN TABLA DE PLUMB DE	
	GROS AVIND D=150 MM SI H=150	
	MM	
36	SA09A1 M -ASIM	60,000
	CONDUCTA INTERIOARA APA RECE	

	DIN PPR	
37	SA11A1 M -ASIM	60,000
	CONDUCTA INTERIOARA APA CALDA	
	DIN PPR	
38	IA22A1 BUC	1,000
	BOILER	
39	SF02A1 M	60,000
	EFFECTUARE PROBA DE ETANS.LA	
	PRES.A INST.INTER.DE APA	
	CU TEVI PVC INCLUSIV	
	ARMATURILE	
40	SD30A1 BUC	5,000
	COT CU RACORD OLANDEZ UA2	
	ZINCAT CU ETANSARE PLANAAVIND	
	INTERIOR SI EXTERIOR CU D= 3 8	
	TOLI	
41	SD01A1 BUC	3,000
	11411-0001;11414-0001	
	ROBINET DE SERVICIU SIMPLU	
42	SA47A1 BUC	4,000
	11434-0001	
	FITING.FONTA MALEAB.MONT.PRIN	
	INSURUB.LA TEVI OTEL ZN.PT.COL.	
	HIDRANTI CU 2 INSURUB.SI D=2	
	TOLI	
43	SA24A1 BUC	4,000
	11401-0001	
	RAMIFICATIE SIMPLA CU MUFE DIN	
	FONTA PT.COND.PRES.LA 45 SAU 90	
	GRADE TUBUL PRINCIPAL AVIND D=	
	50 MM	

44	SB01A1 M -ASIM	60,000
	11426-0001	
	CONDUCTA CANALIZARE MENAJERA	

45	SB04A1 BUC	5,000
	11427-0001	
	COTURI CURBE SAU REDUCTII DE	
	FONTA PT.CANALIZARE ETANS.	
	FRINGHIE GUDRON.SI PLUMB AVIND	
	MM	

46	SB07A1 BUC	3,000
	11431-0001	
	RAMIFIC.SIMPLA SAU MUFA DUBLA	
	DE FONTA PT.CANALIZ.ETANS.	
	FRINGHIE GUDRON SI PLUMB CU D=	

INSTALATII TERMICE

47	IB08A01 BUC -ASIM	18,000
	CALORIFERE	

48	RPCT42A1 BUC	6,000
	DEMONTAREA SOBELOR SI	
	SEMINEURILOR DIN PLACI DE	

49	IC01A1 M -ASIM	105,000
	11309-0001	
	CONDUCTA AGENT TERMIC TUR DIN	
	TEAVA DE PPR	

50	IC01B1 M -ASIM	105,000
	11309-0001	
	CONDUCTA AGENT TERMIC RETUR DIN	
	TEAVA DE PPR	

 INSTALATII DE VENTILARE

51	VC01A1 BUC -ASIM	14,000
	VENTILATOR CU RECUPERARE DE	
	CALDURA	

GREUTAT	TRANSPORT	MATERIALE	MANOPERA	UTILAJE	TOTAL	
---------	-----------	-----------	----------	---------	-------	--

- TRANSPORT CF |
 - ARTICOLE TRA |

- Transport materiale (LEI/T) |
 - Cota aprovizionare |
 - Contributie asigurari sociale |
 - Ajutor somaj |
 - Fond pentru sanatate |
 - Accidente si boli profesionale |
 - Alte chelt. conf. prev. legale |
 - Cheltuieli indirecte |
 - Profit |

TOTAL |

- Taxa pe valoare adaugata |

TOTAL (inclusiv TVA) |

Beneficiar,

Întocmit,
 Ing. Dobre Cătălin - Gabriel



A stylized handwritten signature in blue ink, consisting of a large loop followed by several horizontal strokes.